REGAN YOUNG ENGLAND BUTERA

REFERENDUMS • ENGINEERING • ARCHITECTURE • DESIGN

456 HIGH ST. • MT. HOLLY, NJ 08060 USA (609) 265-2652 • 21Al00912100 • www.RYEBREAD.com



ADDENDUM - 02

DATE:	08 September 2023
FROM:	Scott England, AIA
VIA:	Fax & E-Mail

SUBJECT:
ADDENDUM #2
LINDENWOLD EARLY CHILDHOOD CENTER
RYEB Project #5673C

This addendum is issued to clarify, correct, or supplement the Documents as originally issued and will become a part of the Contract. Receipt thereof shall be acknowledged by Bidders in space provided in the Form of Bid. Failure to acknowledge this Addendum on the official Form of Bid may be cause for rejection of Bid.

2.01 <u>CLARIFICATIONS</u>: Refer to attached Addendum #2, prepared by CME Associates, dated 08 September 2023.

ATTACHMENTS:

1. CME Addendum #2, consisting of 2 pages.

Including this document, Addendum 02 consists of 3 Pages total.

END OF ADDENDUM 02

JOHN H. ALLGAIR, PE, PP, LS (1983-2001)
DAVID J. SAMUEL, PE, PP, CME
JOHN J. STEFANI, PE, LS, PP, CME
JAY B. CORNELL, PE, PP, CME
MICHAEL J. McCLELLAND, PE, PP, CME
GREGORY R. VALESI, PE, PP, CME



TIM W. GILLEN, PE, PP, CME (1991-2019)
BRUCE M. KOCH, PE, PP, CME
LOUIS J. PLOSKONKA, PE, CME
TREVOR J. TAYLOR, PE, PP, CME
BEHRAM TURAN, PE, LSPR
LAURA J. NEUMANN, PE, PP
DOUGLAS ROHMEYER, PE, CFM, CME
ROBERT J. RUSSO, PE, PP, CME
JOHN J. HESS, PE, PP, CME

September 8, 2023

Re: Addendum #2 Lindenwold Early Childhood Center RYEB Project # 5673C

This addendum is issued to clarify, correct, or supplement the Documents as originally issued and will become a part of the Contract. Receipt thereof shall be acknowledged by Bidders in space provided in the Form of Bid. Failure to acknowledge this Addendum on the official Form of Bid may be cause for rejection of Bid.

- 2.1 **CLARIFICATION:** No overall utility site plan is provided. Bidders should review all site drawings for utility locations.
- 2.2 **CLARIFICATION:** Water line shall be 8" Ductile Iron Pipe from the Main to the Meter pit.
- 2.3 <u>CLARIFICATION:</u> Water line shall be wet tapped into existing Main on Gibbsboro Lane as shown on Sheet C9. Contractor is responsible for all applicable County Permits to perform construction within a County Right of Way. See Detail 33 Sheet C13
- 2.4 **CLARIFICATION:** It shall be the responsibility of the contractor to install the water line from Gibbsboro Road to the meter pit.
- 2.5 <u>CLARIFICATION:</u> Refer to Sheet C2 to see how the plans interconnect. Each section is clearly identified as to which sheets correspond to that area.
- 2.6 **CLARIFICATION:** Sheet C4 indicates the 8" sanitary line to be run at 1/8" per foot.
- 2.7 <u>CLARIFICATION:</u> Sheet C4 Indicates the size and type of pipe utilized in the sanitary system. The laterals from the building shall be 4" dia Schedule 40 PVC connected to 8" dia Schedule 40 PVC running to the pump station. The force lateral from to the street is 3" Schedule 40 PVC.
- 2.8 **CLARIFICATION:** The invert of the sanitary line at the pump station should be elevation 92.5 and the exit elevation shall be elevation 95.27.
- 2.9 <u>CLARIFICATION:</u> The sanitary force lateral is shown on sheets C4 and C8. Refer to Sheet C2 to see how the plans interconnect. Each box is clearly identified as to which sheets correspond to that area.



Addendum #2 September 8, 2023

Re: Lindenwold Early Childhood Center

RYEB Project # 5673C Page 2

2.10 **CLARIFICATION:** Refer to Detail 10 on Sheet C12 for the cross section of the pavement.